

**ENGINEERS ESTIMATE OF PROBABLE COSTS  
CDBG PROJECT 08571  
REEDLEY CITY STREET IMPROVEMENT PROJECT PHASE 2**

<b>Item No</b>	<b>Description of Bid Item</b>	<b>Unit</b>	<b>Qty</b>	<b>Unit Price</b>	<b>Total</b>
1	Mobilization	LS	1	12,500.00	12,500.00
2	Insurance and Bonds	LS	1	12,500.00	12,500.00
3	Provide and maintain traffic control as required for construction zones for the duration of the project, complete and in place.	LS	1	12,500.00	12,500.00
4	Cold plane and edge grind each street to provide an uniform surface free of humps, 1/2 inch to 0 (4ft out) at gutter lip and match points, complete and in place.	SY	65,417	1.25	81,771.25
5	Layout, furnish and install thermoplastic striping & pavement markers, striping removal, & temporary striping, complete and in place.	LS	1	25,000.00	25,000.00
6	Furnish and install the specified raised pavement markers per the details provided, complete and in place.	LS	1	4,500.00	4,500.00
7	Furnish and install 3-layer, rubberized, cape seal, complete and in place.	SY	65,417	9.25	605,107.25
8	Furnish and install the specified bituminous asphaltic seal coat per the specification, complete and in place	SY	33,700	0.50	16,850.00
9	Reconstruct failed street section on C Street, complete and in place.	SY	720	35.00	25,200.00
<b>TOTAL:</b>					<b>\$ 795,928.50</b>